The new gutters are then installed, using a special aluminum hanging bracket. These brackets allow for expansion and contraction, without causing any strain on the miters and joints. All miters and joints are fused together using a special aluminum sealant and aluminum rivets.

The existing downspouts appear to be in good condition and the new gutters will connect to them.

INVESTMENT:

Total amount to complete the gutter work as described would be One Thousand Nine Hundred Fifty Dollars.
($1,950.00)

WARRANTY:

The above specification as described would qualify for our Extended Five Year Warranty Program.

FINANCING

We accept Master Card/Visa upon credit approval. You might wish to take advantage of the various programs offered by the card providers, such as "frequent flyer miles". Contact your individual card provider for details and availability.

CLEAN UP:

Debris will be removed from the job site at the end of each working day, leaving the premises in a neat workmanlike manner.

PROTECTION OF PROPERTY:

Procedures shall provide for safe conduct of the work and protection of your property.

Landscaping, concrete walks and curbs shall be protected. Vehicles shall not be driven on walks, or lawns unless proper protection is provided.

INSURANCES:

The above estimate covers all necessary items, including City Permits and Taxes. For your protection, we carry a complete line of insurance, including Workmen's Compensation, Public Liability and Property Damage.

Thank you for giving this proposal your consideration. I look forward to discussing this matter with you in the near future.

Yours very truly,
ELLIOTT & ELLIOTT CO.

Mark R. Nelson